

SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DAR ES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
STERILE SECTION					
844180000000	IV Fluid Manufacturing Machine For Bag		MACHINERY	1	NMB
844120000000	IV Bag Making & Filling Machine		MACHINERY	1	NMB
844120000000	Ampoule Filling & Sealing Machine		MACHINERY	1	NMB
844120000000	Automatic Sticker labelling Machine For Ampoule		MACHINERY	2	PCE
842220000000	Depyrogenation Tunnel		MACHINERY	1	NMB
730900000000	Sterile Manufacturing Complete with Standard Accessories		MACHINERY	1	NMB
901850000000	Ophthalmic Solution Manufacturing Complete with Standard Accessories		MACHINERY	1	NMB
901850000000	Automatic Ophthalmic Filling , Plugging & Capping Machine		MACHINERY	1	NMB
842230000000	Automatic Sticker Labelling Machine		MACHINERY	1	NMB
844319000000	Thermal Inkjet Printer		MACHINERY	7	PCE
841960000000	Double Door Auto Clave - 3 X 3 X 4 feet		MACHINERY	1	NMB
841989000000	Post Sterilization Autoclave - 10000 Liters		MACHINERY	1	NMB
ORAL SOLID DOSAGE					
841939000000	Tablet Granulations UNT 1 120kg Capacity Complete with Standard Accessories		MACHINERY	1	NMB
841939000000	Tablet Granulations UNT 2 60kg Capacity Complete with Standard Accessories		MACHINERY	1	NMB
847979000000	Tablet Punching Sections - 27 Station Complete with Standard Accessories		MACHINERY	2	PCE
847979000000	Tablet Punching Sections - 35 Station Complete with Standard Accessories		MACHINERY	2	PCE
847979000000	Coating Machinery Complete with Standard Accessories		MACHINERY	2	PCE
847979000000	Automatic Alu-Alu & Alu-PVC Blister Packing Machine Complete with Standard Accessories		MACHINERY	5	PCE
842240000000	Automatic Strip Packing Machine Complete with Standard Accessories		MACHINERY	1	NMB
847979000000	Double Cone Blender - 300 Litters for Capsule Section		MACHINERY	1	NMB
847979000000	Capsule Machinery Complete With Standard Accessories		MACHINERY	1	NMB
ORAL LIQUID SECTION					
847989000000	Liquid Manufacturing Complete with Standard Accessories		MACHINERY	1	NMB
847989000000	Automatic Gripper Type Bottle Washing Machine		MACHINERY	1	NMB
847989000000	Automatic Six Head Volumetric Liquid Bottle Filling Machine with 50 ML to 250 ML Syringe Set		MACHINERY	1	NMB
847989000000	Automatic Measuring Cap Placement Machine		MACHINERY	1	NMB
847989000000	Automatic Self Adhesive Vertical Labeling Machine (For Round Container)		MACHINERY	1	NMB
TOPICAL SECTION					
847989000000	Ointment Manufacturing Plant 300 Kgs Capacity		MACHINERY	1	NMB
847989000000	Semi - Auto Double Head Tube Filling Machine for Aluminum & Laminated Tube for filling size 10,15 & 20 grams		MACHINERY	1	NMB
847989000000	Automatic Four Head Airjet Cleaning Machine (Model-GAACM-100) with Acrylic Cover		MACHINERY	2	PCE
847989000000	Automatic Two Head VISCOUS Liquid Bottle Filling Machine (VISCOUS - 2HS) With Servo Motor , PLC & HMI with Acrylic Cover		MACHINERY	1	NMB



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTAA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DARES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
847989000000	Automatic Single Head Screw Capping Machine (Model: GASCM-50) (With Torque Adjustable Head) with Acrylic Cover		MACHINERY	1	NMB
847989000000	Automatic Self Adhesive Round cum Two Side Flat Labeling Machine (Model: GASAL-150RTF) –Without Printer,With Servo Motor, PLC And HMI Label Height Up To 150mm		MACHINERY	1	NMB
847989000000	Nasal Drop Manufacturing & Packaging Line Machineries Complete with Standard Accessories		MACHINERY	1	NMB
847989000000	Automatic Liquid Solution Filling ,Plugging & Capping Machine		MACHINERY	1	NMB
847989000000	Automatic Self Adhesive Round cum Two Side Flat Labeling Machine (Model: GASAL-150RTF) –Without Printer, With Servo Motor, PLC And HMI Label Height Up To 150mm		MACHINERY	1	NMB
842121000000	3000 LTR/ Hr RO COMPLETE WITH STANDARD ACCESSORIES		MACHINERY	1	NMB
840211000000	15 KL Jacketed Storage Tank (Steam)		MACHINERY	1	NMB
847989000000	Turn Table 36"		MACHINERY	4	PCE
847989000000	Table Top Batch Coding Machine for Carton		MACHINERY	6	PCE
847989000000	Packing Table For Tube Line -8 Feet Length		MACHINERY	2	PCE
847989000000	Shrink Tunnel		MACHINERY	3	PCE
842240000000	Flow Wrap Machine		MACHINERY	1	NMB
842240000000	Packing Conveyor Belts 8-12 feet		MACHINERY	18	PCE
842230000000	Carton Sealer (BOPP Taping)		MACHINERY	8	PCE
842230000000	Box Strapping Machine		MACHINERY	8	PCE
	OTHER ACCESSORIES				
902620000000	Leak Test Machines		MACHINERY	6	PCE
845020900000	Washing Machine for Garments		MACHINERY	1	NMB
841950000000	Horizontal Laminar Air Flow		MACHINERY	7	PCE
841950000000	Reverse Laminar Air Flow		MACHINERY	13	PCE
841919000000	Biosafety Cabinete		MACHINERY	1	PCE
841919000000	Mobile LAF		MACHINERY	1	PCE
732421000000	Air Shower		MACHINERY	1	UNT
842382000000	Weight balance (Upto 01 gm To 20 Kg, Table Mounted)		MACHINERY	22	PCE
842382000000	weight balance (Upto 100 gm To 500 Kg)		MACHINERY	16	PCE
731029900000	IPC Bin		MACHINERY	13	PCE
850860000000	Vacuum		MACHINERY	5	PCE
841939000000	Dryer		MACHINERY	5	PCE
732619000000	Liquid Sampler		MACHINERY	2	PCE
732619000000	Powder Sampler		MACHINERY	1	PCE
	HVAC SYSTEMS				
841510000000	Return air duct insulation 13mm & 19 mm RA DUCTING INSULATION: (For all RA Ducting)		UTILITY EQUIPMENTS	140000	MTK
391739000000	25mm dia & 40mm & 50mm MS medium class drain piping with welded fittings & insulated with 25mm rubber insulation up to nearest drainpit		UTILITY EQUIPMENTS	240	MTR
841590000000	AIR HANDLING SYSTEM TERMINAL MOUNTED HEPA FILTER AHU- 2 TO 20 TR, Supply air - 1000 TO 150000 CFM @80-150 mm Static Pressure		UTILITY EQUIPMENTS	100	PCE
841490000000	DUCT IN-LINE FAN UNT FOR EXHAUST AIR		UTILITY EQUIPMENTS	6	PCE



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DARES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
841490000000	Inline -F-01 DIFFERENT CFM (WASH, AHU-F-04) @ 25mm Static Pressure		UTILITY EQUIPMENTS	2	PCE
841490000000	FDV-F-01 1611 CFM @ 65mm Static Pressure - Supply 1611 CFM @ 40mm Static Pressure - Exhaust		UTILITY EQUIPMENTS	6	PCE
841490000000	FDV-G-03 370 CFM @ 65mm Static Pressure - Supply 370 CFM @ 40mm Static Pressure -Exhaust		UTILITY EQUIPMENTS	6	PCE
847190000000	HVAC LOCAL CONTROLS AT AHUS (STAND-ALONE) -HVAC LOCAL CONTROLS TEMP & RH & VFD CONTROLS AT AHU LEVELS ONLY ROOM PRESSURE DIFF INDICATION BY MAGHENALIC GAUGES & ROOM TEMP/RH INDICATION BY DIGITAL DISPLAY TYPE ROOM THERMOMETERS		UTILITY EQUIPMENTS	3	PCE
847190000000	CONTROL CABLING Control cabling, signal, networking & communication cabling between all controllers, sensors, switches, actuators, VFDs, respective AHU panel boards, etc		UTILITY EQUIPMENTS	1	PCE
847190000000	FDV SYSTEM		UTILITY EQUIPMENTS	5	PCE
841490000000	FDV-G-01 3671 CFM @ 65mm Static Pressure - Supply 3671 CFM @ 40mm Static Pressure - Exhaust		UTILITY EQUIPMENTS	1	PCE
841490000000	Magnehelic Room Pressure Gauges		UTILITY EQUIPMENTS	292	PCE
841490000000	DEHUMIDIFIER		UTILITY EQUIPMENTS	2	PCE
841490000000	Volume control damper		UTILITY EQUIPMENTS	450	PCE
841490000000	Dust Collector - Reverse Puls Jet Cleaning 300 & 500 CFM		UTILITY EQUIPMENTS	6	PCE
841490000000	Electrical Cabeling with proper earthing & cable tray Max: 10 Mtr		UTILITY EQUIPMENTS	81	PCE
841490000000	Velocity Sensor		UTILITY EQUIPMENTS	81	PCE
730419000000	SHEET METAL WORKS (for Ducting) 20 swg , 22 swg ,24 swg		UTILITY EQUIPMENTS	140000	MTK
730419000000	GEL TYPE TERMINAL HEPA FILTERS DIFFERENT SIZES & CFM		UTILITY EQUIPMENTS	238	PCE
730419000000	GRILLES & DIFFUSERS DIFFERENT SIZES		UTILITY EQUIPMENTS	532	PCE
730419000000	SS-304 Perforated Grills with volume control damper		UTILITY EQUIPMENTS	450	MTK
730419000000	HVAC ASSORTED SIZE DUCTS		UTILITY EQUIPMENTS	9000	MTR
853710000000	Electrical panel board for , AHU having, switches, starters , contactors , overloaded relays, & Micro process based temprature controler and etc		UTILITY EQUIPMENTS	81	PCE
841590000000	DX Condensing UNT 30 TR , 50 TR , 85 TR ,110 TR		UTILITY EQUIPMENTS	114	PCE
	CLEAN ROOM PARTITIONS				
730890990000	75mm - 90mm ACP SANDWICH PANEL PARTITION - (DOUBLE SKIN PARTITION)		BUILDING MATERIAL	101250	MTK
730890100000	75mm - 90mm ACP SANDWICH PANEL PARTITION - (Double skin Riser)		BUILDING MATERIAL	15000	MTK
730890101000	50mm - 75mm ACP SANDWICH PANEL PARTITION (Double skin Partition)		BUILDING MATERIAL	200000	MTK
730890102000	50mm - 75mm ACP SANDWICH PANEL PARTITION (Walkable Double skin Ceiling)		BUILDING MATERIAL	170000	MTK
73089010300	50mm - 75mm ACP SANDWICH PANEL PARTITION (non Walkable Double skin Ceiling)		BUILDING MATERIAL	182500	MTK
320890000000	Flush type Double skin door with GI powder/epoxy coated sheets		BUILDING MATERIAL	33000	MTK



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DARES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
830160000000	Door Dead lock		BUILDING MATERIAL	662	PCE
830160000000	SS 304 "D" Type Handle		BUILDING MATERIAL	930	PCE
830160000000	Automatic Spring Operated Consealed drop seal		BUILDING MATERIAL	930	PCE
830160000000	Door Closer		BUILDING MATERIAL	661	PCE
830160000000	Concealed Latch		BUILDING MATERIAL	268	PCE
320890000000	Flush type Double skin window for partition with GI epoxy painted spacer with 4mm Clear Glass on both side bonded with VHB tape and Silicon sealant Silica Gell inside		BUILDING MATERIAL	4500	MTK
320890000000	Aluminium Specially designed Powder / epoxy coated coving for partition to partition and partition to ceiling		BUILDING MATERIAL	61500	MTR
320890000000	3mm - 5mm Self leveling Epoxy flooring		BUILDING MATERIAL	16000	MTK
320890000000	75mm Epoxy Coving		BUILDING MATERIAL	10000	MTR
481910000000	Pass Box		BUILDING MATERIAL	51	PCE
711790000000	Pendent		BUILDING MATERIAL	82	PCE
842410000000	Fire Extinguisher		BUILDING MATERIAL	6	PCE
732620000000	Standard Weight With Trolley		BUILDING MATERIAL	2	PCE
732392000000	M S Rack (Sotore) 1000mm width 3 Stacking of 12 MT Height		BUILDING MATERIAL	5000	MTK
392690900000	Spatula & Scoop Set		BUILDING MATERIAL	2	PCE
732690100000	Drain Trap		BUILDING MATERIAL	52	PCE
842123000000	STP		BUILDING MATERIAL	2	PCE
700600000000	Glass Sheet		BUILDING MATERIAL	4320	MTK
700910000000	Mirror (Double Coating Grey)		BUILDING MATERIAL	423	MTK
	BUILDING STRUCTURES				
731420000000	Brc Mesh 1.5mx50m		BUILDING MATERIAL	250	ROLL
940690900000	Pre Fabricated Steel Structural		BUILDING MATERIAL	900000	KGM
	PROCESS UTILITIES				
840211000000	Pure Steam Generator with distribution skid		UTILITY EQUIPMENTS	1	NMB
840211000000	Steam Boiler		UTILITY EQUIPMENTS	1	NMB
841440000000	Air Compressor with distribution skid		UTILITY EQUIPMENTS	1	NMB
840510000000	Nitrogen Generation UNT with distribution skid		UTILITY EQUIPMENTS	1	NMB
840510000000	Oxygen Generation UNT with distribution skid		UTILITY EQUIPMENTS	1	NMB
841960000000	Cooling Tower with Water Chillers		UTILITY EQUIPMENTS	1	NMB
730490000000	ETP 1000 Liters/Hrs With Piping		UTILITY EQUIPMENTS	1	NMB
	WATER PLANT				
842139100000	Vent Filter with Heat Tracer Housing and Hydrophobic type cartridge		UTILITY EQUIPMENTS	1	PCE
721899000000	SS 316L & PTFE Coting ,Capacitance Type Level Transmitter		UTILITY EQUIPMENTS	1	PCE
730719000000	SS 316 ,Spray Ball		UTILITY EQUIPMENTS	1	PCE
903190000000	SS316 ,Compound Pressure GaugeBottom Mounted		UTILITY EQUIPMENTS	1	PCE
702000910000	View glass for tank		UTILITY EQUIPMENTS	1	PCE
903190000000	Rupture Disk without Burst Sensor		UTILITY EQUIPMENTS	1	PCE
940591100000	Light Glass assembly with Lamp and accessories for tank		UTILITY EQUIPMENTS	1	PCE
848140000000	SS304 ,Safety / Vent Valve / Pressure Gauge assembly for jacket		UTILITY EQUIPMENTS	1	PCE
848140000000	Auto On / Off Steam Valve (Piston Valve)		UTILITY EQUIPMENTS	1	PCE
840420000000	Steam Trap Assembly		UTILITY EQUIPMENTS	1	PCE
841950000000	Temperature Controller for Tank		UTILITY EQUIPMENTS	1	PCE
848140000000	SS304 ,Jacket Drain Valve (Ball Valve) TC End15"		UTILITY EQUIPMENTS	1	PCE



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMONI MUNICIPALITY, DAR ES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
848140000000	Tank Drain Valve (Diaphragm Valve) - 2"		UTILITY EQUIPMENTS	1	PCE
841381000000	PW Distribution Pump Capacity - 10 M3/hr @ 20 Bar, 10 HP, (Peak Load - 50 m3/hr)		UTILITY EQUIPMENTS	2	PCE
841381000000	VFD 10 HP		UTILITY EQUIPMENTS	1	PCE
841381000000	Manual Diaphragm Valve at Pump suction, 25" SS 316L, with EPDM diaphragm		UTILITY EQUIPMENTS	1	PCE
841381000000	Manual Diaphragm Valve at Pump Discharge, 20 " SS 316L, with EPDM diaphragm		UTILITY EQUIPMENTS	1	PCE
841381000000	Pump suction 25" & Discharge 20 " and PW supply & return line Piping		UTILITY EQUIPMENTS	1	PCE
902610000000	Pressure Gauge, in supply line, 0-10 kg/cm2, 4" Dial, TC End		UTILITY EQUIPMENTS	2	PCE
902610000000	Flow transmitter on Return Line		UTILITY EQUIPMENTS	1	PCE
841950000000	Temperature Controller for Return Line		UTILITY EQUIPMENTS	1	PCE
841950010000	Conductivity Indicator Cum Controller		UTILITY EQUIPMENTS	1	PCE
848140000000	Fully Automatic ,PLC Based Control Panel with Color HMI Touch Screen Monitor , Screen Size 7" Display , RS-34 Printer Port		UTILITY EQUIPMENTS	1	PCE
848140000000	Actuated 3 Way Flow diverter Valve interconnected with Conductivity Transmitter - 20"		UTILITY EQUIPMENTS	1	PCE
902610000000	Back Pressure Regulating Valve - 20"		UTILITY EQUIPMENTS	1	PCE
902610000000	UV System with Intensity Meters, Panel & Hour meter - API 45		UTILITY EQUIPMENTS	1	PCE
902610000000	SS 304 Skid, Frame to house the system with all supports		UTILITY EQUIPMENTS	1	PCE
902610000000	PU Tubing & Cabeling for PW distribution system		UTILITY EQUIPMENTS	1	PCE
730459000000	Tube, SS316 L, 20"x 16 SWG EP		UTILITY EQUIPMENTS	1200	MTK
730459000000	Bend 316L, 20"x 90 PL EP		UTILITY EQUIPMENTS	200	PCE
730459000000	20" TC liner, SS 316		UTILITY EQUIPMENTS	230	PCE
730459000000	TC Clamp 20", (Investment Casting) - SS 304		UTILITY EQUIPMENTS	158	PCE
730459000000	Silicon Gaskets 20"		UTILITY EQUIPMENTS	158	PCE
730459000000	Sampling Diaphragm Valve - 8 mm		UTILITY EQUIPMENTS	60	PCE
730459000000	Pipe Support assembly 304 20 " BSP at service floor area		UTILITY EQUIPMENTS	230	PCE
730459000000	Pipe support assembly in clean room at user point		UTILITY EQUIPMENTS	200	PCE
730459000000	Manual Operated Zero Dead Leg Valve at User Point, 20", SS 316L, Invest Cast Body with EPDM Diaphragm		UTILITY EQUIPMENTS	60	PCE
730459000000	Orifice Plate at User Point		UTILITY EQUIPMENTS	60	PCE
730459000000	Hose Nipple at User Point TC End		UTILITY EQUIPMENTS	60	PCE
842121000000	Horizontal Multiple Plate Type Sparkler Filter Press (Zero Hold Up Model)		UTILITY EQUIPMENTS	1	NMB
842121000000	Micron Cartridge Filter 02 Nos.		UTILITY EQUIPMENTS	12	PCE
730900000000	Housing for above filter- 02 Nos.		UTILITY EQUIPMENTS	1	NMB
730900000000	500 Ltr Premix Tank		UTILITY EQUIPMENTS	1	NMB
730900000000	5000 Ltrs Manufacturing Tank for LVP with Jacket & with insulation & Bottom Magnetic Stirrer		UTILITY EQUIPMENTS	1	NMB
730900000000	5000 Ltr Holding Tank		UTILITY EQUIPMENTS	1	NMB
847910000000	Mobile CIP / SIP Unit		UTILITY EQUIPMENTS	3	NMB
852290000000	Tray Loader		UTILITY EQUIPMENTS	3	NMB
730900000000	300 Ltrs Mixing Tank		UTILITY EQUIPMENTS	2	NMB
730900000000	300 Ltrs Holding Tank		UTILITY EQUIPMENTS	2	NMB
730900000000	100 Liter Disinfectant Preparation Tank		UTILITY EQUIPMENTS	1	NMB



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DAR ES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
842121000000	Cartridge Filter Housing and Assembly with PG & Vent Valve		UTILITY EQUIPMENTS	1	NMB
730900000000	100 Liter Disinfectant Filtration Tank		UTILITY EQUIPMENTS	1	NMB
732620000000	Additional Trolley Set		UTILITY EQUIPMENTS	1	NMB
903180000000	Visual Inspection		UTILITY EQUIPMENTS	1	NMB
844313000000	Inkjet Printer with Conveyor		UTILITY EQUIPMENTS	1	NMB
842240000000	Packing Conveyor 12 feet		UTILITY EQUIPMENTS	4	PCE
841940000000	Basic Multiple Effect Distillation UNT Water Still 2000 lph to 3000 lph Capacity (WFI Plant)		UTILITY EQUIPMENTS	1	NMB
841940000000	WFI storage tank capacity 10 KL with Accessories		UTILITY EQUIPMENTS	1	NMB
841940000000	PW storage tank capacity 12 KL with Accessories		UTILITY EQUIPMENTS	1	NMB
	LAB EQUIPMENTS				
901600000000	Analytical Balance		LABORATORIES	26	PCE
901600000000	Moisture Balance		LABORATORIES	10	PCE
902480000000	Friability Apparatus		LABORATORIES	5	PCE
902480000000	Leak Test Apparatus		LABORATORIES	5	PCE
902480000000	Disintegration Test Apparatus		LABORATORIES	5	PCE
902480000000	Hardness Tester		LABORATORIES	10	PCE
901790000000	Vernier Calipers		LABORATORIES	10	PCE
903180000000	Bulk Density Measuring		LABORATORIES	10	PCE
903190000000	Viscometers		LABORATORIES	15	PCE
903190000000	pH Meter		LABORATORIES	20	PCE
903190000000	Conductivity Meter		LABORATORIES	15	PCE
701310000000	Glassware Set		LABORATORIES	2	PCE
490199000000	British Pharmacopeia		LABORATORIES	1	PCE
490199000000	US Pharmacopeia		LABORATORIES	1	PCE
902480000000	Friability Apparatus		LABORATORIES	5	PCE
902480000000	Portable Hardness Tester		LABORATORIES	15	PCE
902780000000	Melting Point Apparatus		LABORATORIES	5	PCE
902480000000	HPLC		LABORATORIES	10	PCE
902730000000	UV Spectrophotometer		LABORATORIES	5	PCE
902730000000	FTIR		LABORATORIES	5	PCE
902480000000	Dissolution Test Apparatus		LABORATORIES	5	PCE
902480000000	Disintegration Test Apparatus		LABORATORIES	5	PCE
851490000000	Hot Air Oven		LABORATORIES	2	PCE
851490000000	LOD Oven		LABORATORIES	2	PCE
851490000000	Vacuum Oven		LABORATORIES	2	PCE
851490000000	Hot Plate		LABORATORIES	5	PCE
851490000000	Muffle Furnace		LABORATORIES	2	PCE
841911000000	Fume Hood		LABORATORIES	2	PCE
841989030000	Water Bath		LABORATORIES	2	PCE
841989040000	Magnetic Stirrer		LABORATORIES	3	PCE
842119000000	Centrifuge Machine		LABORATORIES	3	PCE
841989000000	Ultra Sonic Bath		LABORATORIES	2	PCE
841410000000	Vacuum Pump		LABORATORIES	4	PCE
841410000000	UV Cabinet		LABORATORIES	2	PCE
902480000000	Tapped Density Tester		LABORATORIES	2	PCE



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DAR ES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
90248000000	Sieve Shaker		LABORATORIES	2	PCE
90248000000	Hardness Tester		LABORATORIES	5	PCE
90179000000	Vernier Calipers		LABORATORIES	10	PCE
84198900000	Walk-In Stability Chamber		LABORATORIES	2	PCE
84198900000	Humidity Chamber		LABORATORIES	2	PCE
90314900000	Partical Counter		LABORATORIES	2	PCE
90273000000	TOC Offline		LABORATORIES	2	PCE
90314900000	Sonicators		LABORATORIES	2	PCE
90273000000	Refractometer		LABORATORIES	2	PCE
90273000000	Polarimeter		LABORATORIES	2	PCE
84191100000	Distillation UNTs		LABORATORIES	2	PCE
90273000000	Thin Layer Chromatography Kit		LABORATORIES	2	PCE
90273000000	IR Moisture Balance		LABORATORIES	2	PCE
84198900000	Desiccators		LABORATORIES	2	PCE
73242100000	Eye Shower		LABORATORIES	2	PCE
84182900000	Deep Freezer		LABORATORIES	5	PCE
90160000000	Analytical Balance		LABORATORIES	10	PCE
90319000000	pH Meter		LABORATORIES	10	PCE
90319000000	Conductivity Meter		LABORATORIES	10	PCE
84198900000	Autoclave (2X2X4)		LABORATORIES	2	PCE
84198900000	Autoclave (Portable)		LABORATORIES	2	PCE
84198900000	Incubators (42 C to 44 C)		LABORATORIES	1	PCE
84198900000	Incubators (30 C to 35 C)		LABORATORIES	1	PCE
84198900000	BOD Incubators (20 C to 25 C)		LABORATORIES	1	PCE
841989010000	Hot Air Oven		LABORATORIES	2	PCE
841989020000	Hot Plate		LABORATORIES	20	PCE
841989030000	Water Bath		LABORATORIES	2	PCE
841989040000	Magnetic Stirrer		LABORATORIES	2	PCE
841989060000	Colony Counter		LABORATORIES	2	PCE
841989070000	Antibiotic Zone Reader		LABORATORIES	2	PCE
841989090000	Lal Test Kits		LABORATORIES	2	PCE
841989100000	Sterility Test Lits		LABORATORIES	5	PCE
90121000000	Microscope		LABORATORIES	2	PCE
84161000000	Burner		LABORATORIES	5	PCE
	FIRE SAFETY SYSTEMS				
847989000000	Fire Damper		FIRE EQUIPMENT	25	MTR
847989000000	Fusible Link for Fire Dampers		FIRE EQUIPMENT	81	PCE
847989000000	Limit Switch for Fire Dampers		FIRE EQUIPMENT	81	PCE
842410000000	Fire Hose Reel		FIRE EQUIPMENT	224	PCE
842410000000	Fire Extinguisher 9kg Dry Powder		FIRE EQUIPMENT	350	PCE
842410000000	Fire Extinguisher 9 Liters Water		FIRE EQUIPMENT	350	PCE
842410000000	Fire Extinguisher 5kg Carbon Dioxide		FIRE EQUIPMENT	350	PCE
848140000000	Ground Fire Hydrant 100mm Diameter Pillar Type Assocaited With Fittings And Support With 2 Nos Inlets 65mm Diameter Each		FIRE EQUIPMENT	150	PCE
853110000000	Fire Alarm Panel		FIRE EQUIPMENT	66	PCE
853110000000	Optical Smoke Detector		FIRE EQUIPMENT	500	PCE
853110000000	ROR Heat Detector		FIRE EQUIPMENT	500	PCE



SCHEDULE OF MATERIALS

DEVELOPMENT ON PLOT NO.69, BLOCK A, KIZITO KUONJWA MTA, KIMBIJI AREA, KIGAMBONI MUNICIPALITY, DAR ES SALAAM

*HS Code	*Item Name	Model/Specification	*Item Group	*UNT	Quantity approved
85311000000	Strobe & Siren		FIRE EQUIPMENT	500	PCE
85312000000	Manual Call Point -- 2 Leds (Green Led Flash For Working, Red Led On For Alarm)		FIRE EQUIPMENT	500	PCE
85311000000	6" Fire Alarm Bell, Lifco Style		FIRE EQUIPMENT	500	PCE
85311000000	Black Box For Bell		FIRE EQUIPMENT	200	PCE
85312000000	Conventional Fire Alarm Panel And Zones		FIRE EQUIPMENT	120	PCE
85311000000	Head Detectors Complete With Bases		FIRE EQUIPMENT	1010	PCE
85318000000	Break Glass UNTs		FIRE EQUIPMENT	870	PCE
85441100000	Fire Proof Cables		FIRE EQUIPMENT	125000	MTR
WATERPROOFING MATERIALS					
68071000000	Bitumen Felt Roofing Self Finished Consisting of Two Layers		ROOFING MATERIAL	10000	MTK
38244000000	Krytol Membrane Dry Powder Admixture		ROOFING MATERIAL	1880	KGM
57022000000	Coregeotextile		ROOFING MATERIAL	36000	MTK
39031900000	Corecoat Lp (F)		ROOFING MATERIAL	26000	KGM
38246000000	Corecrackfill Paste		ROOFING MATERIAL	6000	KGM
GENERATORS					
85021200000	Diesel Generator 750KVA		BUILDING MATERIALS	2	PCE
85021200000	Diesel Generator 100KVA		BUILDING MATERIALS	1	PCE

